Amendment-VI

Date: 15.9.2016

Ref.: Tender No. HSCC/SJH/Med.Eqpt./2016/21 dt. 19.8.2016.

Sub.: Procurement of Medical Equipment for New Emergency Block & Super-Specialty Block at Safderjung Hospital, New Delhi.

With reference to the above, the amendments issued are as follows:

For Emergency Block Only:

Amended Specifications

Tender Specifications

Modular Multiparameter Monitor with Central Station

- 1.1. Central station for bedside monitors with independently controlled. 21" multi-color TFT Monitor Medical Grade, complete with Ethernet LAN cabling, alarm management, full disclosure of all the waveforms for 72 hours trending, bed to bed viewing of waveforms and remote alarm management like silencing of alarms etc. Central stationshould be valid USFDA approved with certification.
- 1.2 Central Station to have capability to display atleast 16 beds

Equipment Specifications for Complete Monitoring System

- 2. Description of Function
- 2.1 Critical patients need to be monitored continuously in ICU and bedside with central monitors
- 3. Operational Requirements
- 3.1 ICU should comprise of modular monitors at the bedside and with central station.
- 3.2 Capability of storage of patient data
- 3.3 Demonstration of the equipment is a must.
- 3.4. Technical Specifications
- 3.5 Multi colored TFT/LCD display of sizes as specified.
- 3.6 Eight digital and waveforms/traces display
- 3.7 Combination of single, dual and multi parameter modules.
- 3.8 Parameter modules freely exchangeable between all the monitors.

3.9 Multi-channel ST segment analysis.
3.10 Facility to monitor and display ECG, Respiration, NIBP, SPO2(Masimo technology), Temp. 2 channel
3.11 Monitor should have 12-lead ECG Monitoring capability simultaneously.
3.12 Automatic arrhythmia detection & alarm for standard and lethal arrhythmia.
3.13 EtCO2 – Side stream/main stream. Display both inspired and expired values, showing capnography
3.14 Should provide hemodynamic, oxygenation, Ventilation calculation package.
3.15 Should have drug calculation package.
3.16 Trend of at least 72 hours for 19" & 21 Monitors, 24 hours trending for 15" monitor.
3.17 Monitors should be HL7 compatible.
3.18 Minimum 50 nos. event recall/snapshot facility automatically triggered by alarm.
3.19 EEG, BIS, NMT,3 additional IBP's- modules to be offered as per the nos. specified which help clinicians in guiding fluid management.
3.20.Web browsing facility to review each network monitors data through hospital LAN via office PC in Hospital LAN Network and / or through dial up facility from remote location.
3.21. The monitors should have monitor-to monitor overview facility
3.22. Deleted
3.23. System should be complete with Computer System, UPS with 1 hour back-up & Laser Printer for each Central Station.
3.24. The system offered should not be PC based.
3.25 System including Modules should be valid USFDA approved with certification.
No. of Central Stations with 60 displays & facility to support dual screen (Minimum 21" - 20 nos.)
No.of Monitors (Minimum 19" - 70 nos., Minimum 15" - 120 nos.)
3.26 List of additional Modules to be providde in 19" Monitors
Three IBP (in each of 20 nos. Monitors)
Cardiac output (in each of 15 nos. Monitors)
End tidal CO2 (in each of 70 nos. Monitors)

NMT (in each of 5 nos. Monitors) EEG (in each of 10 nos. Monitors) Venous saturation (in each of 70 nos. Monitors) BIS (in each of 25 nos. Monitors) Spirometry (in each of 33 nos. Monitors) Minimal Invasive CCO (in each 70 nos. Monitors) Non-Invasive Hb (in each 70 nos. Monitors) Network Recording Modules (40no.) - Deleted All the above modules should be campatible with 15" & 19" Monitors. 3.25 Accessories ECG Module (5 lead ECG cable- 2 sets per monitor, 6/10 lead ECG cable-1 set per monitor) SpO₂ Probe complete set (2 for Adult, 1 for Pediatric, 1 for neonatal) NIBP cuff complete set (3 per monitor for adult, 2 for pediatric, 1 for neonatal) End tidal CO2 (Adult & Ped. kit 01 per Monitor & Disposables sample lines – 50 tubing per monitor) IBP Reusable Interface Cable (3 per monitor) Disposable pressure transducer kit (10 per monitor) Two Temperature (Rectal/ esophageal & skin probes per monitor) Recorder paper rolls (10 per module)- Deleted BIS Sensors - 20no. For each module Spirometry: Suitable monitoring set for each monitor Accessories for Cardiac Output: One set for each monitor Venous saturation - suitable monitoring for each monitor **NMT Monitoring Set** EEG Monitoring set for each monitor **4.0 General Specifications**

4.01 Comparative compliance statement to be provided, mentioning page and para in the catalogue.

4.02 Undertaking that Local after sales Service will be provided round the clock

4.03 Undertaking from Principal that after sales service, spares & accessories will be provided for minimum 10 years after installation.

4.04 Warranty for minimum five years and CMC as per rules.

4.05 All installation and cabling to be done on turn key basis and cost to be borne by the bidder.

4.06 Bidder to inspect site of installation before quoting, to confirm the site of wall mounts and length of cables to be installed.

4.07. Service and user manual in English

5. Environmental factors: No interference with use of electrocautry

5.1 The unit shall be capable of being stored continuously in ambient temperature of 0 - 50deg C and relative humidity of 15-90%.

5.2 The unit shall be capable of operating continuously in ambient temperature of 10 -40 deg C and relative humidity of 15-90%.

Shall meet valid IEC-60601-1-2: 2001general Requirements of Safety for Electromagnetic Compatibility.

6. Power Supply

6.1 Power input to be 220-240VAC, 50Hz fitted with Indian plug

6.2 Shall meet the safety requirements as per IEC 60601-2-27:1994—Medical electrical equipment—Part 2: Particular requirements for the safety of electrocardiographic monitoring equipment

Revised EMD amount is INR 14,22,800/-. Bid submission date is 22.9.2016.

All other tender terms and conditions remain unchanged.

Amendment to be issued will be uploaded on websites www.tenderwizard.com/HSCC & www.hsccltd.com.

Medical Superintendent Safderjung Hospital & VMMC, New Delhi.