LRSI

LALA RAM SARUP INSTITUTE OF TUBERCULOSIS & RESPIRATORY DISEASES, NEWDELHI

Tender

for

Supply Installation Testing & Commissioning of Gas Pipeline System for Private Ward at LRS Institute of Tuberculosis & Respiratory Diseases New Delhi

VOLUME - III

PRICE BID

January, 2012



(Consultants & Engineers for Mega Hospitals & Laboratories) E - 6 (A), Sector - I, NOIDA (U.P.) - 201 301 (INDIA)

PHONE: 91-2542436, 2542440 FAX: 91-11-91-2542447

Tender No. HSCC/LRSI/PG-1/106/LAUNDRY/2012

BILL OF QUANTITY

PART-I
SUPPLY INSTALLATION AND COMMISSIONING OF MEDICAL GAS MANIFOLD SYSTEM WITH 2 YEARS WARRANTY IN PVT. WARDS OF LRSI,
NEWDELHI
All the equipments should be from ISO certified Company

| | | | | UNIT RATE IN Rs. | | |
|---------|-----------------------------------|------|-----|------------------|-----------------------------|---------------------------|
| SI. No. | ITEM DESCRIPTION | UOM | QTY | (IN FIGURE) | UNIT RATE IN Rs. (IN WORDS) | AMOUNT IN Rs. (IN FIGURE) |
| 1 | COPPER PIPE 12 MM OD X 0.7 MM THK | MTR. | 100 | | | |
| 2 | COPPER PIPE 15 MM OD X 0.9 MM THK | MTR. | 550 | | | |
| 3 | COPPER PIPE 22 MM OD X 0.9 MM THK | MTR. | 220 | | | |
| 4 | OXYGEN GAS OUTLET | NUM | 40 | | | |
| 5 | VACUUM OUTLET | NUM | 40 | | | |
| 6 | OXYGEN FLOW METER 0-15 LPM | NUM | 40 | | | |
| 7 | WARD VACUUM UNIT 600ML | NUM | 40 | | | |
| 8 | ALARM-2GAS SERVICES (DIGITAL) | NUM | 2 | | | |
| 9 | ZONAL VALAVE BOX -2GAS | NUM | 2 | | | |
| | OXYGEN LOW PRESSURE SILICON | | | | | |
| 10 | RUBBER TUBE | MTR. | 80 | | | |
| | HIGH PRESSURE ANTISTATIC TUBE FOR | | | | | |
| 11 | OXYGEN | MTR. | 60 | | | |
| | HIGH PRESSURE ANTISTATIC TUBE FOR | | | | | |
| 12 | VACUUM | MTR. | 60 | | | |
| 13 | ISOLATION VALVE -15 MM | NUM | 56 | | | |
| 14 | BED HEAD UNIT | NUM | 40 | | | |
| | SUB TOTAL (FIGURE) | | | | | · |

IN WORDS: RUPEES

" PART - II "

| 1 | Comprehensive Maintenance -3 Years:- | | | | | |
|-------|--|----------|--------|---------------------------------|-----------------------------|---------------------------|
| | | UOM | QTY | UNIT RATE IN Rs. (IN FIGURE) | UNIT RATE IN Rs. (IN WORDS) | AMOUNT IN Rs. (IN FIGURE) |
| | Providing on-site comprehensive maintenance for a period of 3 years after successful completion of warranty period for Part I. The onsite comprehensive maintenance shall include all spares including replacements/repairs as required. | | | | | |
| 1 | Year 1 (One) from the date of satisfactory completion of warranty period | LS | 1 | | | |
| 2 | Year 2 (Two) from the date of satisfactory completion of Year 1 | LS | 1 | | | |
| 3 | Year 3 (Three) from the date of satisfactory completion of Year 2 | LS | 1 | | | |
| | SUB TOTAL (FIGURE) SUMMARY OF RATES QUOTED | | | | | |
| 1 | TOTAL (PART-I) | | | | | |
| 2 | TOTAL (PART-II) | | | | | |
| Grand | Total Amount (PART - I + PART - I | I) (in F | igures |) :- | | |

IN WORDS : RUPEES

Date

Signature of Bidder Name of Bidder Seal of the Bidder

The above quoted rates will be inclusive of all taxes, duties and other charges. Cost of CMC will be added for ranking purpose

LOCATION OF TERMINALS

| SI. No. | Floor | Total Rooms | | OXYGEN OUTLETS | VACUUM OUTLETS | FLOWMETER | WARD VACUUM UNIT | OXYGEN LOW PRESSURE SILICON RUBBER TUBE IN MTR. | HIGH PRESSURE TUBE FOR OXYGEN IN MTR. | HIGH PRESSURE TUBE FOR VACUUM IN MTR. | ISOLATION LINE VALVE-15 | ZONAL VALVE BOX-2 GAS | ALARM-2 GAS | BED HEAD UNIT |
|---------|-----------|-------------|--------|----------------|----------------|-----------|------------------|---|---------------------------------------|---------------------------------------|-------------------------|-----------------------|-------------|---------------|
| 1 | GR. FLOOR | 8 | SINGLE | 8 | 8 | 8 | 8 | 16 | 12 | 12 | 16 | 1 | 1 | 8 |
| 2 | GR. FLOOR | 6 | DOUBLE | 12 | 12 | 12 | 12 | 24 | 18 | 18 | 12 | 0 | 0 | 12 |
| 3 | 1st FLOOR | 8 | SINGLE | 8 | 8 | 8 | 8 | 16 | 12 | 12 | 16 | 1 | 1 | 8 |
| 4 | 1st FLOOR | 6 | DOUBLE | 12 | 12 | 12 | 12 | 24 | 18 | 18 | 12 | 0 | 0 | 12 |
| | | | | | | | | | | | | | | |
| | | TOTAL | | 40 | 40 | 40 | 40 | 80 | 60 | 60 | 56 | 2 | 2 | 40 |